

File No: 8873-8330 Government of India Ministry of Environment, Forest and Climate Change (Issued by the State Environment Impact Assessment Authority(SEIAA), UTTAR PRADESH) ***



Date 20/06/2024



T		
To,		
	Sh <mark>ri Pra</mark> halad Singh	
	M/s AGARWAL ASSOCIATES PROMOTERS I	LIMITED
	Village-Shahpur, Bamheta, Pargana-Dasna, Tehsil	l & district-Ghaziabad, U.P. , Shahpur Bamheta,
	GHAZIABAD, UTTAR PRADESH, , 201002	
	prahalad@agarwalassociatesgroup.com	
Subject:	-	the proposed project under the provision of the EIA
		p Project "Aditya World City" at Khasra No 1619,
		73 , 2292, 2293, 2294, 2295, 2354,2364 , 2365 , 2366 ,
		74, 2375, Village Shahpur, Bamheta Ghaziabad, M/s
	Agarwal Associates (Promoters) Ltd.	
Sir/Madam,		
Shiftinuunii,	This is in reference to your application	submitted to SEIAA vide proposal number
		for grant of prior Environmental Clearance (EC) to
	the proposed project under the provision of the EL	
	2. The particulars of the proposal are as below :	
	C G R P	
	(i) EC Identification No.	EC24B3812UP5485066N
	(ii) File No.	<mark>8873</mark> -8330
	(iii) Clear <mark>ance Typ</mark> e	Fresh EC
	(iv) Category	B1
	(v) Duciost/Activity Included Cabadula No	8(b) Townships/ Area Development Projects /
	(v) Project/Activity Included Schedule No.	Rehabilitation Centres
		Proposed Integrated Township Project " Aditya
	(vii) Name of Project	World City'' at village Shahpur, Bamheta
	(vii) Plane of Project	Ghaziabad (U.P.) by M/s Agarwal Associates
		(Promoters) Ltd.
	(viii) Name of Company/Organization	AGARWAL ASSOCIATES PROMOTERS
		LIMITED
	(ix) Location of Project (District, State)	GHAZIABAD, UTTAR PRADESH
	(x) Issuing Authority	SEIAA
	(xi) Applicability of General Conditions as per	No

EIA Notification, 2006

3. In view of the particulars given in the Para 1 above, the project proposal interalia including Form-2(Part A, B and C)/ EIA & EMP Reports were submitted to the SEAC for appraisal under the provision of EIA notification 2006 and its subsequent amendments.

4. The above-mentioned proposal has been considered by SEAC in its meeting held on 17-05-2024. The minutes of the meeting and all the project documents are available on PARIVESH portal which can be accessed from the PARIVESH portal by scanning the QR Code above.

5. Details of the minerals to be mined along with production capacity and the brief on the salient features of the project as submitted by the project proponent in Form 1 (Part A and B) in the reports and as presented during SEAC meeting are annexed to this EC as Annexure (2).

6. The SEAC, in its meeting held on 17-05-2024, based on information submitted viz: Form 1 (Part A, B and C), EIA/EMP report etc & clarifications provided by the project proponent and after detailed deliberations on all technical aspects and public hearing issues and compliance thereto furnished by the Project Proponent, recommended the proposal for grant of Environment Clearance under the provision of EIA Notification, 2006 and as amended thereof subject to stipulation of Specific and Standard EC conditions as given in Annexure (1).

7. The SEIAA in its meeting held on 06-06-2024 has examined the proposal in accordance with the provisions contained in the Environment Impact Assessment (EIA) Notification, 2006 & further amendments thereto in its meeting dated 11-03-2024 and based on the recommendations of the SEAC hereby accords Environment Clearance for the instant proposal to Shri Prahalad Singh under the provisions of EIA Notification, 2006 and as amended thereof subject to compliance of the Specific conditions as given in Annexure (1)

8. The SEIAA reserves the right to stipulate additional conditions, if found necessary.

9. The Environmental Clearance to the aforementioned project is under provisions of EIA Notification, 2006. It does not tantamount to approvals/consent/permissions etc. required to be obtained under any other Act/Rule/regulation. The Project Proponent is under obligation to obtain approvals /clearances under any other Acts/ Regulations or Statutes, as applicable, to the project.

10. The PP is under obligation to implement commitments made in the Environment Management Plan, which forms part of this EC.

11. General Instructions:

a) The project proponent shall prominently advertise it at least in two local newspapers of the District or State, of which one shall be in the vernacular language within seven days indicating that the project has been accorded environment clearance and the details of SEIAA website where it is displayed.

b) The copies of the environmental clearance shall be submitted by the project proponents to the Heads of local bodies, Panchayats and Municipal Bodies in addition to the relevant offices of the Government who in turn must display the same for 30 days from the date of receipt.

c) The project proponent shall have a well laid down environmental policy duly approved by the Board of Directors (in case of Company) or competent authority, duly prescribing standard operating procedures to have proper checks and balances and to bring into focus any infringements/deviation/violation of the environmental / forest / wildlife norms / conditions.

d) Action plan for implementing EMP and environmental conditions along with responsibility matrix of the project proponent (during construction phase) and authorized entity mandated with compliance of conditions (during operational phase) shall be prepared. The year wise funds earmarked for environmental protection measures shall be kept in separate account and not to be diverted for any other purpose. Six monthly progress of implementation of action plan shall be reported to the Ministry/Regional Office along with the Six-Monthly Compliance Report.

e) Concealing factual data or submission of false/fabricated data may result in revocation of this environmental clearance and attract action under the provisions of Environment (Protection) Act, 1986.

f) The project proponent shall also ensure that the proposed site is not a part of any no-development zone as required/prescribed/identified under law. In case of violation, this permission shall automatically deem to be cancelled. Also, in the event of any dispute on ownership or land use of the proposed site, this clearance shall automatically deem to be cancelled.

g) Any appeal against this EC shall lie with the National Green Tribunal, if preferred, within a period of 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.

h) The SEIAA reserves the right to revoke the environmental clearance, if conditions stipulated are not implemented to the satisfaction of SEIAA. SEIAA may impose additional environmental conditions or modify the existing ones, if necessary.

Specific EC Conditions for (Townships/ Area Development Projects / Rehabilitation Centres)

1. Environmental Attributes

S. No	EC Conditions
1.1	 Since this is Township and Area Development project in which area for different purposes has been allotted, separate Environmental Clearance shall be taken for Group housing & commercial development including health centre etc. having built-up area more than 20,000 sqm as per the provision of ELA Notification 2006 (as amended). Project proponent is advised to explore the possibility and getting the cement in a closed container rather through the plastic bag to prevent dust emissions at the time of loading/unloading. Project proponent should ensure that there will be no use of "Single use of Plastic" (SuP). In compliance to Hon'ble Supreme Court order dated 13/01/2202 in IA no. 158128/2019 and 158129/2019 in Writ petition no. 13029/1985 (MC Mehta Vs. Gol and others) anti-smog guns shall be installed to reduce dust during excavation. The project proponent will comply the use of fuel for backup power as per guidelines issued by CPCB from time to time. The project proponent will comply the use of fuel for backup power as per guidelines issued by CPCB from time to time. The project proponent authority. In case of any mismatch/deviation, amended environmental clearance will be obtained by project proponent. In case of failure, the granted environmental clearance shall automatically deem to be cancelled. The project proponent shall ensure that the project site does not attract/infringe any buffer zone, wethand zone etc. of no activity identified/declared under law. Criteria/ norms provided by competent Authority regarding the seismic zone are followed for construction work. Provision of alarm system, to timely notify the residents, in case of cacurrence of earthquak/other natural disasters/fire should be provided. A well defined evacuation plan should also be prepared and regular mock drills should be rooted movients. Rise of stars should be constructed in a way, so that it should provide smooth movemen

S. No	EC Conditions
	 14. The project proponent will ensure the quality of construction water as per standards and specifications of relevant codes in order to prevent possible corrosion in concrete, reinforcements and other structural components in order to avoid adverse social and environmental impacts. 15. The project proponent will ensure exploitation of maximum possible potential of solar energy generation in the proposed project area and prefer to use it instead of conventional electricity in order to reduce the Green House Gas Emission causing climate change. 16. The project proponent will make necessary arrangement to get Structural auditing conducted by an expert institution once in 05 years during life span of the building to ensure safe life of the residents and prevent environmental and social hazards. 17. The project proponent shall plan for storm water management drained with appropriate slope and length so that the flood water could get a passage to release in a short span of time.
1.2	 The project proponent shall submit the details of STP like no. of modules etc. The project proponent shall ensure to plant broad leaf trees of local and indigenous species and their maintenance. The CPCB guidelines in this regard shall be followed. The project proponent shall submit within the next 3 months the details on quantification of year wise CER activities along with cost and other details. The CER activities should be related to mitigation of Environmental Pollution and awareness for the same like water harvesting pits and carbon sequestration parks / designed ecosystems .At least one school in the vicinity of project area should be provided with rooftop solar plant, toilets in public place or in school of nearby villages and if there is a girl's school then girls toilet properly equipped with overhead water tank should be constructed. Name of the school adopted for installation of roof top solar plant should be displayed on the website of project proponent shall submit within the next 3 months the details of estimated construction waste generated during the construction period and its management plan. The project proponent shall submit within the next 3 months the details of segregation plan of MSW. The project proponent shall ensure that waste water is properly treated in STP and treated water should be reused for gardening flushing system and washing etc. For reuse of water for irrigation system shall be installed and maintained for proper function. Part of the treated swage, if discharged to sew line, shall meet the prescribed standards for the discharge and shall be done with necessary permissions from concerned authorities. Under any circumstances untreated sewage shall not be discharged to municipal sewer line or any nearby water body. The project proponent will ensure that proper dust control arrangements are made during construction and proper display board is installed at the site to inform the public t

S. No	EC Conditions
	 submitted by PP for seeking EC. In case approved building plan is different from the one submitted for seeking EC then this EC will stand null and void. 14- In compliance to Hon'ble Supreme Court order dated 13/01/2020 in IA no. 158128/2019 and 158129/2019 in Writ petition no. 13029/1985 (MC Mehta Vs GOI and others) anti-smog guns shall be installed to reduce dust during excavation. 15- DG sets shall be gas based and Guidelines issued by CAAQMS for NCR region regarding the use of DG sets during construction and operational phase should be followed. 16- The project proponent shall install organic bio converter. 17- Project Proponent shall submit the Six-monthly Compliance on the Environment Clearance condition prescribed in the Prior Environment Clearance letter as per MoEF&CC OM F.no- IAS-22/01/2022-IA-III (E-172624) Dated 14-06-2022. 18- The effluent from STP after tertiary treatment shall be subjected to ozonation to avoid foul smell. 19- The project proponent shall submit within the next 3 months the details of solar power plans for solar electrification beyond 10% within the project. 20- The Bio Medical Waste shall be disposed in nearest CBWTF as per the govt issued guidelines in this regard.

Standard EC Conditions for (Townships/ Area Development Projects / Rehabilitation Centres)

1. Statutory Compliance

S. No	EC Conditions	
1.1	The project proponent shall obtain all necessary clearance/ permission from all relevant agencies including town planning authority before commencement of work. All the construction shall be done in accordance with the local building byelaws.	
1.2	The approval of the Competent Authority shall be obtained for structural safety of buildings due to earthquakes, adequacy of firefighting equipment etc. as per National Building Code including protection measures from lightening etc.	
1.3	The project proponent shall obtain forest clearance under the provisions of Forest (Conservation) Act, 1980, in case of the diversion of forest land for non-forest purpose involved in the project.	
1.4	The project proponent shall obtain clearance from the National Board for Wildlife, if applicable.	
1.5	The project proponent shall obtain Consent to Establish / Operate under the provisions of Air (Prevention & Control of Pollution) Act, 1981 and the Water (Prevention & Control of Pollution) Act, 1974 from the concerned State Pollution Control Board/ Committee.	
1.6	The project proponent shall obtain the necessary permission for drawl of ground water / surface water required for the project from the competent authority.	
1.7	A certificate of adequacy of available power from the agency supplying power to the project along with the load allowed for the project should be obtained.	
1.8	All other statutory clearances such as the approvals for storage of diesel from Chief Controller of Explosives, Fire Department, Civil Aviation Department shall be obtained, as applicable, by project	

S. No	EC Conditions	
	proponents from the respective competent authorities.	
1.9	The provisions of the Solid Waste Management Rules, 2016, e-Waste (Management) Rules, 2016, and the Plastics Waste Management Rules, 2016, shall be followed.	
1.10	The project proponent shall follow the ECBC/ECBC-R prescribed by Bureau of Energy Efficiency, Ministry of Power strictly.	

2. Air Quality Monitoring And Preservation

S. No	EC Conditions
2.1	Notification GSR 94(E) dated 25.01.2018 of MoEF&CC regarding Mandatory Implementation of Dust Mitigation Measures for Construction and Demolition Activities for projects requiring Environmental Clearance shall be complied with.
2.2	A management plan shall be drawn up and implemented to contain the current exceedance in ambient air quality at the site.
2.3	The project proponent shall install system to carryout Ambient Air Quality monitoring for common/criterion parameters relevant to the main pollutants released (e.g. PM10 and PM2.5) covering upwind and downwind directions during the construction period.
2.4	Diesel power generating sets proposed as source of backup power should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all proposed DG sets. Use of low sulphur diesel. The location of the DG sets may be decided with in consultation with State Pollution Control Board.
2.5	Construction site shall be adequately barricaded before the construction begins. Dust, smoke & other air pollution prevention measures shall be provided for the building as well as the site. These measures shall include screens for the building under construction, continuous dust/ wind breaking walls all around the site (at least 3-meter height). Plastic/tarpaulin sheet covers shall be provided for vehicles bringing in sand, cement, murram and other construction materials prone to causing dust pollution at the site as well as taking out debris from the site.
2.6	Sand, murram, loose soil, cement, stored on site shall be covered adequately so as to prevent dust pollution.
2.7	Wet jet shall be provided for grinding and stone cutting.
2.8	Unpaved surfaces and loose soil shall be adequately sprinkled with water to suppress dust.
2.9	All construction and demolition debris shall be stored at the site (and not dumped on the roads or open spaces outside) before they are properly disposed. All demolition and construction waste shall be managed as per the provisions of the Construction and Demolition Waste Management Rules 2016.
2.10	The diesel generator sets to be used during construction phase shall be low sulphur diesel type and

S. No	EC Conditions
	shall conform to Environmental (Protection) prescribed for air and noise emission standards.
2.11	The gaseous emissions from DG set shall be dispersed through adequate stack height as per CPCB standards. Acoustic enclosure shall be provided to the DG sets to mitigate the noise pollution. Low sulphur diesel shall be used. The location of the DG set and exhaust pipe height shall be as per the provisions of the Central Pollution Control Board (CPCB) norms.
2.12	For indoor air quality the ventilation provisions as per National Building Code of India.

3. Water Quality Monitoring And Preservation

S. No	EC Conditions
3.1	The natural drain system should be maintained for ensuring unrestricted flow of water. No construction shall be allowed to obstruct the natural drainage through the site, on wetland and water bodies. Check dams, bio-swales, landscape, and other sustainable urban drainage systems (SUDS) are allowed for maintaining the drainage pattern and to harvest rain water.
3.2	Buildings shall be designed to follow the natural topography as much as possible. Minimum cutting and filling should be done.
3.3	Total fresh water use shall not exceed the proposed requirement as provided in the project details.
3.4	The quantity of fresh water usage, water recycling and rainwater harvesting shall be measured and recorded to monitor the water balance as projected by the project proponent. The record shall be submitted to the Regional Office, MoEF&CC along with six monthly Monitoring reports.
3.5	A certificate shall be obtained from the local body supplying water, specifying the total annual water availability with the local authority, the quantity of water already committed, the quantity of water allotted to the project under consideration and the balance water available. This should be specified separately for ground water and surface water sources, ensuring that there is no impact on other users.
3.6	At least 20% of the open spaces as required by the local building bye-laws shall be pervious. Use of Grass payers, payer blocks with at least 50% opening, landscape etc. would be considered as pervious surface.
3.7	Installation of dual pipe plumbing for supplying fresh water for drinking, cooking and bathing etc and other for supply of recycled water for flushing, landscape irrigation, car washing, thermal cooling, conditioning etc. shall be done.
3.8	Use of water saving devices/fixtures (viz. low flow flushing systems; use of low flow faucets tap aerators etc) for water conservation shall be incorporated in the building plan.
3.9	Separation of grey and black water should be done by the use of dual plumbing system. In case of single stack system separate recirculation lines for flushing by giving dual plumbing system be done.
3.10	Water demand during construction should be reduced by use of pre-mixed concrete, curing agents

S. No	EC Conditions
	and other best practices referred.
3.11	The local bye-law provisions on rain water harvesting should be followed. If local bye-law provision is not available, adequate provision for storage and recharge should be followed as per the Ministry of Urban Development Model Building Byelaws, 2016. Rain water harvesting recharge pits/storage tanks shall be provided for ground water recharging as per the CGWB norms.
3.12	A rain water harvesting plan needs to be designed where the recharge bores of minimum one recharge bore per 5,000 square meters of built up area and storage capacity of minimum one day of total fresh water requirement shall be provided. In areas where ground water recharge is not feasible, the rain water should be harvested and stored for reuse. The ground water shall not be withdrawn without approval from the Competent Authority.
3.13	All recharge should be limited to shallow aquifer.
3.14	No ground water shall be used during construction phase of the project.
3.15	Any ground water dewatering should be properly managed and shall conform to the approvals and the guidelines of the CGWA in the matter. Formal approval shall be taken from the CGWA for any ground water abstraction or dewatering.
3.16	The quantity of fresh water usage, water recycling and rainwater harvesting shall be measured and recorded to monitor the water balance as projected by the project proponent. The record shall be submitted to the Regional Office, MoEF&CC along with six monthly Monitoring reports.
3.17	Sewage shall be treated in the STP with tertiary treatment. The treated effluent from STP shall be recycled/re-used for flushing, AC make up water and gardening. As proposed, no treated water shall be disposed in to municipal drain.
3.18	No sewage or untreated effluent water would be discharged through storm water drains.
3.19	Onsite sewage treatment of capacity of treating 100% waste water to be installed. The installation of the Sewage Treatment Plant (STP) shall be certified by an independent expert and a report in this regard shall be submitted to the Ministry before the project is commissioned for operation. Treated waste water shall be reused on site for landscape, flushing, cooling tower, and other end-uses. Excess treated water shall be discharged as per statutory norms notified by Ministry of Environment, Forest and Climate Change. Natural treatment systems shall be promoted.
3.20	Periodical monitoring of water quality of treated sewage shall be conducted. Necessary measures should be made to mitigate the odour problem from STP.
3.21	Sludge from the onsite sewage treatment, including septic tanks, shall be collected, conveyed and disposed as per the Ministry of Urban Development, Central Public Health and Environmental Engineering Organization (CPHEEO) Manual on Sewerage and Sewage Treatment Systems, 2013.

4. Noise Monitoring And Prevention

S. No	EC Conditions
4.1	Ambient noise levels shall conform to residential area/commercial area/industrial area/silence zone both during day and night as per Noise Pollution (Control and Regulation) Rules, 2000. Incremental pollution loads on the ambient air and noise quality shall be closely monitored during construction phase. Adequate measures shall be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards by CPCB / SPCB.
4.2	Noise level survey shall be carried as per the prescribed guidelines and report in this regard shall be submitted to Regional Officer of the Ministry as a part of six-monthly compliance report.
4.3	Acoustic enclosures for DG sets, noise barriers for ground-run bays, ear plugs for operating personnel shall be implemented as mitigation measures for noise impact due to ground sources.

5. Energy Conservation Measures

S. No	EC Conditions
5.1	Compliance with the Energy Conservation Building Code (ECBC) of Bureau of Energy Efficiency shall be ensured. Buildings in the States which have notified their own ECBC, shall comply with the State ECBC.
5.2	Outdoor and common area lighting shall be LED.
5.3	Concept of passive solar design that minimize energy consumption in buildings by using design elements, such as building orientation, landscaping, efficient building envelope, appropriate fenestration, increased day lighting design and thermal mass etc. shall be incorporated in the building design. Wall, window, and roof u-values shall be as per ECBC specifications.
5.4	Energy conservation measures like installation of CFLs/ LED for the lighting the area outside the building should be integral part of the project design and should be in place before project commissioning.
5.5	Solar, wind or other Renewable Energy shall be installed to meet electricity generation equivalent to 1% of the demand load or as per the state level/ local building bye-laws requirement, whichever is higher.
5.6	Solar power shall be used for lighting in the apartment to reduce the power load on grid. Separate electric meter shall be installed for solar power. Solar water heating shall be provided to meet 20% of the hot water demand of the commercial and institutional building or as per the requirement of the local building bye-laws, whichever is higher. Residential buildings are also recommended to meet its hot water demand from solar water heaters, as far as possible.

6. Waste Management

S. No	EC Conditions	
6.1	A certificate from the competent authority handling municipal solid wastes, indicating the existing civic capacities of handling and their adequacy to cater to the M.S.W. generated from project shall be obtained.	

S. No	EC Conditions	
6.2	Disposal of muck during construction phase shall not create any adverse effect on the neighbouring communities and be disposed taking the necessary precautions for general safety and health aspects of people, only in approved sites with the approval of competent authority.	
6.3	Separate wet and dry bins must be provided in each unit and at the ground level for facilitating segregation of waste. Solid waste shall be segregated into wet garbage and inert materials.	
6.4	Organic waste compost/Vermiculture pit/Organic Waste Converter within the premises with a minimum capacity of 0.3 kg /person/day must be installed.	
6.5	All non-biodegradable waste shall be handed over to authorized recyclers for which a written tie up must be done with the authorized recyclers.	
6.6	Any hazardous waste generated during construction phase, shall be disposed off as per applicable rules and norms with necessary approvals of the State Pollution Control Board.	
6.7	Use of environment friendly materials in bricks, blocks and other construction materials, shall be required for at least 20% of the construction material quantity. These include Fly Ash bricks, hollow bricks, AACs, Fly Ash Lime Gypsum blocks, Compressed earth blocks, and other environment friendly materials.	
6.8	Fly ash should be used as building material in the construction as per the provision of Fly Ash Notification of September, 1999 and amended as on 27th August, 2003 and 25th January, 2016. Ready mixed concrete must be used in building construction.	
6.9	Any wastes from construction and demolition activities related thereto shall be managed so as to strictly conform to the Construction and Demolition Waste Management Rules, 2016.	
6.10	Used CFLs and TFLs should be properly collected and disposed off/sent for recycling as per the prevailing guidelines/ rules of the regulatory authority to avoid mercury contamination.	

7. Green Cover

7. Green Cover	CAC GREEN		
S. No	EC Conditions		
7.1	No tree can be felled/transplant unless exigencies demand. Where absolutely necessary, tree felling shall be with prior permission from the concerned regulatory authority. Old trees should be retained based on girth and age regulations as may be prescribed by the Forest Department. Plantations to be ensured species (cut) to species (planted).		
7.2	A minimum of 1 tree for every 80 sqm of land should be planted and maintained. The existing trees will be counted for this purpose. The landscape planning should include plantation of native species. The species with heavy foliage, broad leaves and wide canopy cover are desirable. Water intensive and/or invasive species should not be used for landscaping.		
7.3	Where the trees need to be cut with prior permission from the concerned local Authority, compensatory plantation in the ratio of 1:10 (i.e. planting of 10 trees for every 1 tree that is cut) shall be done and maintained. Plantations to be ensured species (cut) to species (planted). Area for green belt development shall be provided as per the details provided in the project document.		

S. 1	No	EC Conditions	
7.4		Topsoil should be stripped to a depth of 20 cm from the areas proposed for buildings, roads, paved areas, and external services. It should be stockpiled appropriately in designated areas and reapplied during plantation of the proposed vegetation on site.	

8. Transport

S. No	EC Conditions	
8.1	A comprehensive mobility plan, as per MoUD best practices guidelines (URDPFI), shall be prepared to include motorized, non-motorized, public, and private networks. Road should be designed with due consideration for environment, and safety of users. The road system can be designed with these basic criteria. a. Hierarchy of roads with proper segregation of vehicular and pedestrian traffic. b. Traffic calming measures. c. Proper design of entry and exit points. d. Parking norms as per local regulation.	
8.2	Vehicles hired for bringing construction material to the site should be in good condition and should have a pollution check certificate and should conform to applicable air and noise emission standards be operated only during non-peak hours.	

9.

S. No	EC Conditions		
9.1	A detailed traffic management and traffic decongestion plan shall be drawn up to ensure that the current level of service of the roads within a 05 kms radius of the project is maintained and improved upon after the implementation of the project. This plan should be based on cumulative impact of all development and increased habitation being carried out or proposed to be carried out by the project or other agencies in this 05 Kms radius of the site in different scenarios of space and time and the traffic management plan shall be duly validated and certified by the State Urban Development department and the P.W.D./ competent authority for road augmentation and shall also have their consent to the implementation of components of the plan which involve the participation of these departments.		

10. Human Health Issues

S. No	G-Payre Conditions	
10.1	All workers working at the construction site and involved in loading, unloading, carriage of construction material and construction debris or working in any area with dust pollution shall be provided with dust mask.	
10.2	For indoor air quality the ventilation provisions as per National Building Code of India.	
10.3	Emergency preparedness plan based on the Hazard identification and Risk Assessment (HIRA) and Disaster Management Plan shall be implemented.	
10.4	Provision shall be made for the housing of construction labour within the site with all necessary infrastructure and facilities such as fuel for cooking, mobile toilets, mobile STP, safe drinking	

S. No	EC Conditions	
	water, medical health care, crèche etc. The housing may be in the form of temporary structures to be removed after the completion of the project.	
10.5	Occupational health surveillance of the workers shall be done on a regular basis.	
10.6	A First Aid Room shall be provided in the project both during construction and operations of the project.	

11. Miscellaneous

S. No	EC Conditions	
11.1	The project proponent shall prominently advertise it at least in two local newspapers of the District or State, of which one shall be in the vernacular language within seven days indicating that the project has been accorded environment clearance and the details of MoEFCC/SEIAA website where it is displayed.	
11.2	ii. environmental clearance shall be submitted by the project proponents to the Heads of local bodies, Panchayats and Municipal Bodies in addition to the relevant offices of the Government who in turn has to display the same for 30 days from the date of receipt.	
11.3	The project proponent shall upload the status of compliance of the stipulated environment clearance conditions, including results of monitored data on their website and update the same on half-yearly basis.	
11.4	The project proponent shall submit six-monthly reports on the status of the compliance of the stipulated environmental conditions on the website of the ministry of Environment, Forest and Climate Change at environment clearance portal.	
11.5	The company shall have a well laid down environmental policy duly approved by the Board of Directors. The environmental policy should prescribe for standard operating procedures to have proper checks and balances and to bring into focus any infringements/deviation/violation of the environmental/forest/wildlife norms/conditions. The company shall have defined system of reporting infringements/deviation/violation of the environmental/forest/wildlife norms/conditions of the environmental/forest/wildlife norms/conditions and/or shareholders/stake holders. The copy of the board resolution in this regard shall be submitted to the MoEF&CC as a part of six-monthly report.	
11.6	A separate Environmental Cell both at the project and company head quarter level, with qualified personnel shall be set up under the control of senior Executive, who will directly report to the head of the organization.	
11.7	Action plan for implementing EMP and environmental conditions along with responsibility matrix of the company shall be prepared and shall be duly approved by competent authority. The year wise funds earmarked for environmental protection measures shall be kept in separate account and not to be diverted for any other purpose. Year wise progress of implementation of action plan shall be reported to the Ministry/Regional Office along with the Six Monthly Compliance Report	
11.8	The project proponent shall submit the environmental statement for each financial year in Form-V to the concerned State Pollution Control Board as prescribed under the Environment (Protection)	

S. No EC Conditions		
	Rules, 1986, as amended subsequently and put on the website of the company.	
11.9	The project proponent shall inform the Regional Office as well as the Ministry, the date of financial closure and final approval of the project by the concerned authorities, commencing the land development work and start of production operation by the project.	
11.10	The project authorities must strictly adhere to the stipulations made by the State Pollution Control Board and the State Government.	
11.11	The project proponent shall abide by all the commitments and recommendations made in the EIA/EMP reportand also that during their presentation to the Expert Appraisal Committee.	
11.12	No further expansion or modifications in the plant shall be carried out without prior approval of the Ministry of Environment, Forest and Climate Change (MoEF&CC).	
11.13	Concealing factual data or submission of false/fabricated data may result in revocation of this environmental clearance and attract action under the provisions of Environment (Protection) Act, 1986.	
11.14	The Ministry may revoke or suspend the clearance, if implementation of any of the above conditions is not satisfactory.	
11.15	The Ministry reserves the right to stipulate additional conditions if found necessary. The Company in a time bound manner shall implement these conditions.	
11.16	The Regional Office of this Ministry shall monitor compliance of the stipulated conditions. The project authorities should extend full cooperation to the officer (s) of the Regional Office by furnishing the requisite data / information/monitoring reports.	
11.17	The above conditions shall be enforced, inter-alia under the provisions of the Water (Prevention & Control of Pollution) Act, 1974, the Air (Prevention & Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986, Hazardous and Other Wastes (Management and Transboundary Movement) Rules, 2016, and the Public Liability Insurance Act, 1991 along with their amendments and Rules and any other orders passed by the Hon'ble Supreme Court of India / High Courts and any other Court of Law relating to the subject matter.	
11.18	Any appeal against this EC shall lie with the National Green Tribunal, if preferred, within a period of 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.	

12. Specific Conditions

S. No	EC Conditions	
12.1	The project proponent shall develop R& D facilities to develop their own technologies for propylene and polypropylene processing.	

Additional EC Conditions

N/A

A presentation was made by the project proponent along with their consultant M/s Environmental and Technical Research Centre to SEAC on 17-05-2024.

Project Details Informed by the Project Proponent and their Consultant

The project proponent, through the documents and presentation gave following details about their project –

- The environmental clearance is sought for Integrated Township Project "Aditya World City" at Khasra No.- 1619, 1622, 1623, 1625, 1670, 1671/1, 1671/2,1672, 1673, 2292, 2293, 2294, 2295, 2354,2364, 2365, 2366, 2367, 2368, 2369, 2370, 2371,2372, 2373, 2374, 2375, Village Shahpur, Bamheta Ghaziabad, M/s Agarwal Associates (Promoters) Ltd.
- Environmental Clearance for the earlier proposal was granted by SEIAA, U.P. vide Ref. No. 1555/Parya/SEAC/1602/2012/DD(D)dated 07/10/2013 for the Plot area 7,47,435.0 sqm and built-up area is 13,95,596.098 sqm.
- 3. The standard terms of reference of the present proposal was issued through online Parivesh Portal on 10/10/2023 and EIA report submitted by the project proponent on 20/03/2024.
- 4. Details of constructed built-up area of the project site:
- Approx 531814.413 sqm built-up area has been constructed against the proposed built-up area 1395596.098 Sqm which is 38.10 % of total proposed built-up area.

S.No.	Particulars	Builtup Area (Sqm.)
01	Group Housing	375013.506
02	EWS/LIG	18709.147
03	School	12503.241
04	Plotted Area	112881.560
05	Health centre	1707.897
06	Temple	1390.832
07	Commercial-1	9308.230
08	Sub-Station	300.00
	Total	531814.413

5. Salie	<mark>nt featur</mark> es of the p	roject:	<u>s</u>	
Item		Details		
Name and Location of the		Proposed Integrated Township Project "Aditya World City" at Village:		
Project		Shahpur, Bamheta, Ghaziabad, Uttar Pradesh		
Developers of the project		M/s Agarwal Associates (Promoters) Ltd.		
Total Plot Area		748695.0 sq. m. (74.86 Hectares approx)		
Net Plot Area		747435 sq. m.		
Built-u <mark>p A</mark>	rea	13,95,596.098 sq. m		
Total Water Requirement		It is estimated that the total water demand during the construction phase will		
		be 60 KLD and during operation phase total water demand will be 5,536 KLD		
		and Fresh water requirement is 3778 KLD.		
Power Requirement		32,000 kVA, Source: Paschimanchal Vidyut Vitaran Nigam Ltd		
Power Backup		DG sets of total capacity 1000 KVA (10 nos.)		
Total Parking Proposed		Requirement : 6,749 ECS as per bye Laws		
		Proposed : 8,630 ECS		
Solid Waste to be Generated		32442.05 Kg/Day Municipal waste will be generated.		
		Out of total 19465.23 Kg/Day will be the organic waste and 9.099 Kg/Day		
		horticulture waste will be generated.		
Rain wate	r harvesting pits	27		
Total Proje	ect Cost	INR 32500 Lakhs		
Solar Light	ts	2880 KW Solar Panel		
6. Land	use details:			
Sr.No.	Land Use		Area in Sqm	Area in Percentage(%)
1	Roof Top (Building	Roof Top (Building , Covered Shed)		8.62
2	Green Belt Area		27655.10	3.7
3	Road & Paved		92009.25	12.31
4 Open Area			563341.76	75.37

	Total 7474	35.00 100.00
7. De	etailed area statement of the project:	·
S. No.	Particulars	Area (in m ²)
1	Total License Area	748695
2	Area Under Ponds	1260
3	Net Plot area	747435
4	Area Under Master Plan of Ghaziabad	52,371,84
	Master Plan Green Belt (30 m wide)	34,376.87
	Master plan Road (45 m wide)	17,994.97
5.	Net Planning Area	695,063.16
	Plotted (A)	180,544.65
	Total Group Housing including green area (B)	184,109.60
	Group Housing	1,56,469.6
	Green in Group housing	27,640
	EWS/LIG (C)	18,575.52
	Total Commercial area including green area (D)	31,766.89
	Commercial	28,590.2
	Green in commercial	3176.69
	Public/semi public	52,171.44
	Anganwadi (E)	1, <mark>5</mark> 38.37
	Nursery School (F)	6,659.35
	Primary school (G)	6,191.56
	High school (H)	8,136.94
	Inter collage (I)	12036.56
	Health center (J)	3,293.91
	Sub post office (K)	366.95
	Police Chowki (L)	3,052.43
	Rail Reservation Center (M)	451.80
	Community Cum marriage Hall (N)	1,528.28
	Temple (O)	1,038
	Dustbins	960
		4,068.99
	Sub station	,
	STP	3,591.50
	Green/ open	73,589.62
-	Road area	154,305.44
6	GC as per Ghaziabad Bye Laws	
	Total permissible & Proposed Ground Coverage	212,927.22
_	Plotted @60% of A	108,326.79
	Group Housing @50% of B	64,438.36
	Commercial @50% of D	15,883.45
	Anganwadi @ 35% of E	538.43
	Nursery School @40% of F	2,663.74
	Primary School @ 35% of G	2,167.05
	High School @ 35% of H	2,847.93
	Inter college @ 35% of I	4,212.79
	Health Centre @ 40% of J	1,317.56
	Post Office @ 10% of K	36.69
	Police chowki @ 10% of K	305.24
	Rail Reservation Centre @ 10% of M	45.18
	Community cum marriage hall @ 40% of N	611.31
	Temple @ 40% of O	415.2
	EWS/LIG @ 49.1%	9,117.50
7	FAR as per Ghaziabad Bye Laws	
	Total Permissible and proposed FAR Area	11,09,386.31
	Plotted @ 2.00	361,089.30
	Group Housing @3.75	5,86761.00
	Commercial Area @ 2.75	78,623.00

	Angenuedi @1	1,538.37
	Anganwadi @1	
	Nursery School @0.80	5,327.48
	Primary School @1	6,191.56
	High School @1.2	9,764.328
	Inter college @1.2	14,443.87
	Health Center @ 1.5	4,940.865
	Post office @ 0.10	36.695
	Police chowki @0.10	305.24
	Rail Reservation Center @ 0.10	45.18
	Rail Reservation Center @ 0.10	45.18
	Community cum marriage hall @ 1.5	2,292.42
	Temple @1.5	1,557
	EWS/LIG @2	36,470
8	Service Area	8,620.49
	Dustbins	960
	Sub station	4,068.99
	STP	3,591.50
9	Basement Area	2,77,589.30
10	Built Up Area	13,95,596.098
11	Total Landscape Area including water body green belt	173,674.338
	Water Body	
	Master Plan Green Belt	34,891.158
	Green in Group Housing	34,376.87
	Green in commercial	27,640
-	G-1	3176.69
	G-2	3,733.28
	G-3	4,583.30
	G-3A	677.35
	G-4	711.58
	G-5	3,933.64
	G-6	222.51
	G-7	20095.95
	G- 8	827.97 4,663.79
	G- 9	2,390.06
	G- 9 G-10	1,587.92
		3,852.66
	G-11 G-12 G-13	10,321.87
	G-13	15,987.74
8 50	lid waste details:	

Facilities Dusy ideal		1.1	Tatal	
Facilities Provided	Waste generation norms per	Unit	Total waste	
	unit		generated (kg/day)	
Residential	0.5 kg/cap/day	<mark>5</mark> 7495	28747.5	
	Payment	persons (
Staff	0.25 kg/cap/day	12218	3054.5	
		persons		
Health Centre	Bio Medical Waste (0.38	50 beds	19	
(assuming 50)	kg/bed/day)			
Bedded	General Hospital waste	50 beds	75	
	(1.25/bed/day)			
	Staff (0.25kg/cap/day)	50	12.5	
	Visitor (0.15kg/cap/day)	226	33.9	
Visitors	0.15kg/cap/day	4267	640.05	
Landscape waste	45.49 @ 0.2 kg/acre/day			
(acres)			9.099	
Total solid waste genera			32,591.55	

waste

	Rural Education Facility and Infrastructure Development	Activities Upgradation of School infrastructure & Educational facilities- Provide Interactive smart class equipment's /gadgets/solar	Rs. 155 Lakhs (Govt. school at Village: Shahpur Bamheta & Mahrauli) 30 nos potable water facilities - Rs. 40 lakhs, Solar panels installation- Rs. 25 lakhs,	Rs. 105 Lakhs- (Govt school at Village: Girdharpur Sunarsi & Naiphal) 15 nos potable water facilities -Rs. 20 lakhs, Solar panels installation- Rs.	260
	R I	panels like desktop computers, projectors, Interactive White Boards and distributing study materials, school bags, sports equipment's etc. to students, Seating Benches, installation of potable water facilities, construction of sanitized toilets	Rs 20 lakhs for desktop computers, projectors, Interactive White Boards and distributing study materials, school bags, sports equipment, white washing of school walls, Rs. 20 lakhs for construction of sanitized toilets, Rs 10 lakhs for E-learning setup. Rs 40 Lakhs for maintenance of School building, Furniture etc.	30 lakhs, Rs 10 lakhs for desktop computers, projectors, Interactive White Boards And distributing study materials, school bags, sports equipment, white washing of school walls, Rs. 12 lakhs for construction of sanitized toilets, Rs 8 lakhs for E-learning setup. Rs 25 Lakhs for maintenance of School building, Furniture etc.	
2.	Community (Skill training And Livelihood)	etc. Skill development for youth, Women empowerment- Organizing Training programs, center development for youth/residents, providing scholarship.	Rs. 50 Lakhs (Govt. school at Village: Shahpur Bamheta & Mahrauli) Rs. 30 lakhs allocated for Organizing training programs regarding EMP, Solid waste & fly ash management, environment monitoring, that will Benefited to approx. 150 youth and 100 women, Rs. 20 lakhs for scholarship	Rs. 50 lakhs (Village: Girdharpur Sunarsi & Naiphal) Rs. 25 lakhs allocated for Organizing training programs regarding EMP, Solid waste & fly ash management, environment monitoring, that will Benefited to approx. 150 youth and 100 women, Rs. 25.0 lakhs for scholarship to 30 students of village.	100
3.	Up gradation of healthcare facilities	Provision of oxygen cylinders, medical instruments etc.	to 30 students of village. Rs. 30 lakhs (Village: Girdharpur Sunarsi & Naiphal) Provision of 10 oxygen cylinders- Rs. 15 lakhs, Rs 10 lakhs for improving medical infrastructures, Rs. 10 lakhs for providing medical instruments, medicines, surgical kits etc.)	Rs. 50 Lakhs (Govt. school at Village: Shahpur Bamheta & Mahrauli) Provision of 20 oxygen cylinders- Rs. 30 lakhs, Rs 10 lakhs for improving medical infrastructures, Rs. 10 lakhs for providing medical instruments, medicines, surgical kits etc.)	80
4.	Plantation development	Plantation / Avenue plantation along roadside, tree plantation in nearby schools / colleges / vacant land/Panchayat bhavan / Govt Office, etc.	Rs. 20.5 Lakhs (1400 no's in Village: Girdharpur Sunarsi & Naiphal)	Rs. 27 Lakhs (2000 no's in Village: Shahpur Bamheta & Mahrauli) Grand Total (Rs)	47.5

10. The project proposal falls under category–8(b) of EIA Notification, 2006 (as amended).

Copy, through email, for information and necessary action to -

- 1. Additional Chief Secretary, Department of Environment, Forest and Climate Change, Government of Uttar Pradesh, Lucknow (email – psforest2015@gmail.com)
- 2. Joint Secretary, Ministry of Environment, Forest and Climate Change, Government of India, 3rd Floor, Prithvi-Block, Indira Paryavaran Bhawan, Jor Bagh Road, New Delhi-110003 (email – sudheer.ch@gov.in)
- 3. Deputy Director General of Forests (C), Integ rated Regional Office, Ministry of Environment, Forest and Climate Change, Kendriya Bhawan, 5th Floor, Sector "H", Aliganj, Lucknow 226020 (email rocz.lko-mef@nic.in)
- 4. District Magistrate, Ghaziabad.
- 5. Member Secretary, Uttar Pradesh Pollution Control Board, TC-12V, Paryavaran Bhawan, Vibhuti Khand, Gomti Nagar, Lucknow-226010 (email <u>ms@uppcb.com</u>)
- 6. Copy for Guard File.

(Sanjeev Kumar Singh) Member Secretary, SEIAA

Capacity of the second seco